

<b><u>GENERAL ABSTRACT</u></b>				
<b><u>PART- A</u></b>				
SCHEDULED ITEMS		=	Rs.	
TOTAL-A		=	Rs.	
<b><u>PART-B</u></b>				
NON-SCHEDULED ITEMS		=	Rs.	
TOTAL-B		=	Rs.	
TOTAL(A+B)		=	Rs.	<b>0</b>
G.TOTAL		=	Rs.	<b>0</b>
SAY		=	Rs.	<b>0</b>
IN MILLION		=	Rs.	<b>0.000</b>

**Please Noted: Premium Quoted by bidders shall be included with Cartage & Interim Relief -**

<b>B.O.Q FOR THE CONSTRUCTION OF</b>					
<b>WALKWAY WITH FIBER MESH SHADE</b>					
<b>QUAID-E-AWAM UNIVERSITY ENGINEERING SCIENCE &amp; TECHNOLOGY NAWAHSHA</b>					
<b>SCEDHULED ITEM (PART-A)</b>					
Sr. No	Item Description	QTY	Unit	Rate	Amount
1	Jungle clearance and removing of Garbage (b) Thick	31200	% SFT	151.25	47190
2	Excavation Chapter -1 item 4a	11050	% CFT	5747.5	63509.875
3	Cement concrete brick or stone ballast 1 1/2" to 2" gauge. (b) Ratio 1 : 4 : 8	10436	% CFT	9416.28	982693.44
4	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering. (i) Ratio. 1: 4 :8	4902	% CFT	11288.75	553336.90
5	PCC 1:2:4 at edges of Masonary top	432.5	% CFT	14429.25	62406.50625
6	Pacca brick work in foundation and plinth in: (b) Cement sand mortar 1:3	1946.25	% CFT	12989.4	252806.1975
7	Providing & fixing cement paving blocks flooring having size of 197 x 97 x 60 (mm) of city / quddra / cobble shape with pigmented, having strength b/w 5000 psi to 8500 psi l/c filling the joints with hill sand and laying in specified manner/ pattern and design etc: complete.	12110	SFT	223.97	2712276.7
				<b>SUM PKR =</b>	<b>4674219.618</b>
				<b>PREIMUM QOUATED ABOVE/BELOW (%) =</b>	
				<b>TOTAL =</b>	

<b>Non- SCEDHULED ITEM (PART-B)</b>					
Sr. No	Item Description	QTY	Unit	Rate	Amount
NS-1	Back Fill Soil (silt or Silty clay)	11029	CFT		
NS-2	P/F of Shade with round 16 Guage pipe inlcuding cuting, welding, fixing, coloring inclding fixing of (1' X12') size Fiber Mesh blue in color a per the attached drawing the specification shall be followed as given in drawing (Note: 1' Gape shall be provided every 50' Span)	12110	SFT		
			<b>SUM PKR</b>		
			<b>GRAND TOTAL (SUM A+B)</b>		
<b>Amount In Words:</b>					

**Please Noted: Premium Qouated by bidders shall be included with Cartage & Interim Relief -**